



**Network Administrator Settings:** All communication between the DXi irrigation controller and Sentinel WMS central software is routed through the Toro Cloud Connect Server, hosted on AWS. Network Administrators will need to ensure firewall allows the following port(s):

- Outbound Port 443 (HTTPS) for connection from Sentinel WMS central software to the Toro Cloud Connect Server, URL: **cloudconnect.toro.com**

For controllers that are connected to an organization's LAN network via Wi-Fi or Ethernet

- Outbound Ports 5101-5199 for connection from DXi irrigation controller to the Toro Cloud Connect Server, URL: **dx.cloudconnect.toro.com**

# TORO CLOUD CONNECT SERVER & PORTS

Controllers connected via Ethernet, Cellular, or WiFi



## Firewall Access


DXi: 50.112.190.84 Ports: 5101-5199  
Laguna: 50.112.190.84 Port: 10001  
WMS/App: 52.32.180.203 Port: 443 (HTTPS)



Laguna



WMS



ProMax Connect